

Builder	Foruminvest nv
Architect	Robbrecht & Daem
Study team	TV Technum - Tractebel
Delivery	30-03-2010
Description	- Demolition work - Groundwork -

- Demolition work - Groundwork Asbestos decontamination - Soil
decontamination - Sewerage works Diaphragm walls for excavation (4
underground levels) - Tunnel
construction according to Stross
method. - Underground levels carried
out according to Stross method. Concrete structure construction: Outside wall panels of architectural
concrete, natural stone, brickwork and
wall covering - Outside wall carpentry of
aluminium, steel and wood Waterproofing via hot roof and dome
principle

